

सुदूरपश्चिम प्रदेश सरकार
भूमी व्यवस्था, कृषि तथा सहकारी मन्त्रालय
पशुपन्छी तथा मत्स्य विकास निर्देशनालय
भेटेरीनरी अस्पताल तथा पशु सेवा विज्ञ केन्द्र
धनगढी, कैलाली

Bill of Quantity

Name of Project:- Repairing works in Buffalo Shade and Office Building

Location:- Tikapur, Kailali

S. N.	Description of items	Unit	Quantity	Rate (NRS)		Amount	Remarks
				In Figure	In Words		
1	Earth work Excavation for foundation in Soft soil including 30m lead and 1.5 m lift, disposal with safe tipping site	Cu.M.	6.56				
2	Stone sooling in Footing & Flooring	Cu.M.	8.83				
3	Providing and placing M10 (1:3:6) cement concrete for the foundation and footing etc. including compaction, curing, testing and lead 30m. etc. all complete as per specification and drawing.	Cu.M.	17.16				
4	Good quality local chimney made Brickwork in 1:4 C/S mortar in perfect line level finish including supply of materials, wetting the bricks, racking the joints and curing the work for at least 7 days all complete as per approved drawing, Specification and instruction of site engineer.	Cu.M.	24.96				
5	12.5mm thick cement plaster in 1:4 cement mortar in wall inside & outside with smooth finish in line & level including wetting the surface and curing all complete in wall outside the building.	Sq.m	155.64				
6	3mm Neat Cement Punning	Sq.m	194.05				
7	RCC works with M15 1:2:4 concrete	Cu.M.	3.60				
8	MS Reinforcement Steel	Kg	289.22				
9	Repairing and Maintenance of office Building, Septic Tank including placing of ready slab RCC cover, pipe fitting including PVC pipe, elbow, socket and other fittings as per instuction of Engineer.	Job	1.00				

Contractor Sign:-

Firm:-

Approved Sign:-

Designation:-

सुदूरपश्चिम प्रदेश सरकार
भूमी व्यवस्था, कृषि तथा सहकारी मन्त्रालय
पशुपन्छी तथा मत्स्य विकास निर्देशनालय
भेटेरीनरी अस्पताल तथा पशु सेवा विज्ञ केन्द्र
धनगढी, कैलाली

10	Maintenance of buffalo farm entrance iron door fitting including Welding as per instuction of Engineer.	Job	1.00				
11	Providing and Fixing of Saal wood Door frame	Cum	0.05				
12	Providing and Fixing of Saal wood Door Shutter with all necessary fittings	Sq.m	2.31				
13	Earth Filling in various place including compaction	Cum	54.42				
Total							
Add 13% for VAT							
Grand Total							

Contractor Sign:-

Firm:-

Approved Sign:-

Designation:-